

Kerite Cable Services Project Profile

Project	Walden Line Circuit 862
Client	NYSEG
Location	Walden, NY
Cable Design	115 kV, 2000 kcmil CU – High Voltage Cable
Length	1,650 Circuit feet
Subcontractor(s)	Anderson & Wood Construction Company
Scope	Observed cable being pulled into an existing duct bank. KCS installed 12-G&W PAT 140 terminations and cable shield ground equipment. Upon completion of the installation a final system acceptance test was conducted.



115kV 2000 kcmil cable being pulled into existing ducts.



3- G&W PAT 140 installed on Riser Pole