

Kerite Cable Services Project Profile

Project	Big Tree Substation
Client	NYSEG
Location	Buffalo, NY
Cable Design	138 kV, 1000 kcmil CU
Length	1,500 Circuit feet
Subcontractor(s)	Anderson & Wood Construction Company
Scope	Supervised cable pull into owner supplied duct bank. KCS technicians built 12- G&W PAT 140 termination with assistance from Anderson & Wood Construction.



Prepping the cable for 10kV jacket test.



Completed G&WPAT 140.