

Kerite Cable Services Project Profile

Project	Podick Substation
Client	NUSCO
Location	Amherst, MA
Cable Design	115 kV, 1000 kcmil CU
Length	675 Circuit feet
Subcontractor(s)	Central Connecticut Cable
Scope	Pulled cable through owner supplied duct bank, assemble 6 G&W PAT 140 terminals, install grounding link boxes and provided final acceptance testing.



KCS Technicians securing the cable to aluminum cable stands.



KCS's subcontractor manipulating the cable in order to secure to riser structure.