

Kerite Cable Services Project Profile

Project	Webster Substation
Client	NUSCO
Location	Franklin, MA
Cable Design	115 kV, 1000 kcmil CU
Length	705 Circuit feet
Subcontractor(s)	Central Connecticut Cable
Scope	Pull cable through owner supplied duct bank, assemble 6 G&W PAT 140 terminals, install grounding link boxes and provide final acceptance testing.



Pulling the cable up the riser structure and securing to a cable stand.



KCS technicians prep cable for terminal connector.